

**ENGINEERING DEPARTMENT  
UNIVERSITY OF DELHI  
DELHI-110007**

Ref. No. UE/ 392

/DU/M- 54 (2017-2018)

dated 11/07/18


**NOTICE INVITING QUOTATION**

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work **"Repair of rusted G.I. watre pipe line at A-3 (29-31) Probyn Road, University of Delhi ."** So as to reach the office of the undersigned upto 3.00 P.M. on 21/3/18

Sl. No.	Item	Qty	Unit	Rate	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.25	cum	5466.30	1367
2	Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with Jamuna sand, with common burnt clay non modular bricks.	2.5	sqm	498.95	1247
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.25	cum	892.70	223
4	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 15 mm dia nominal bore	12	metre	215.10	2581
5	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 50 to 80 mm nominal bore	2	each	761.10	1522
6	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 15 mm nominal bore	4	each	165.25	661
7	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	2	each	610.65	1221
8	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./ H.P.H.D. plastic ball. 20 mm nominal bore, 120 mm long, weighing not less than 198 gms	2	each	285.60	571
9	Disposal of malba and other kooda (waste items) garbage and disposal out side the campus	1	cum	2960.00	2960
10	Repairing of G.I. pipe line upto 50mm dia. i/c excavations & checking tracing etc. complete. For digging the line i/c searching, dismantling cc and excavation	1	each	2500.00	2500.00
				<b>Total</b>	<b>14853.00</b>

**Condition:**

- The work should be completed in 05 days.
- 1.5% water charges will be deducted.
- Rates should be quoted both in words & figures.
- The contractor must visit the site before quoting his rates.
- CPWD specification in force will be followed.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.



**Executive Engineer**

I/we hereby quote..... % above/below/at par on the estimated cost of **Rs.14853/-**


Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- The Director, Computer Center with a request to display the Notice Inviting quotation on the Delhi University Website.
- Sh. Jacob John, J.E. (C)
- Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- Notice Board



**Executive Engineer**