

ENGINEERING DEPARTMENT

UNIVERSITY OF DELHI

DELHI-110007

QUOTATION

Ref. No. UE/ 139

/DU/M- (2014-2015) dated

9/9/14

Sealed percentage rate quotations are hereby invited from the contractors enlisted with CPWD, MES, Railways and any Govt./ public sector undertaking and working contractor of Delhi University for the work "Repair wall plaster, distempering, painting, repairing by welding damaged door/ window shutter etc at Mansarowar Hostel, University of Delhi" So as to reach the office of the undersigned upto 3.00 P.M. on16/9/14


S. No	Description of Items	Unit	Qty	Rate	Amount
1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	sqm	1082	79.65	86181
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	320	63.05	20176
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	48	221.15	10615
4	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm	sqm	4	651.40	2606
5	Providing and fixing ISI marked oxidised M.S. pressed butt hinges with necessary screws etc. complete. 75x47x1.70 mm	each	33	20.7	683
6	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 300x16 mm	each	30	161.55	4847
7	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete 200x10 mm	each	30	56.3	1689
8	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	cum	6	123.85	743
9	Providing and applying birla / JK wall putty on wall surface (one or more coats) as required in thickness upto 1 mm i/c sand papering etc to prepare smooth as per direction of Engineer-in-charge.	cum	850	57	48450
10	Repair of door window i/c taking out, repair & refixing etc complete by welding	each	24	334	8016
11	Renewing fly proof galvanised MS wire gauge to window and clerestory windows using wire gauge with average widths of of operature 1.4 mm in both diverging with of dia 0.63 mm all complete with wooden fillets etc / beading where necessary.	sqm	8	712	5696
				Total	189703

Condition:

- The work should be completed in 10 days.
- 1.50 % water charges will be deducted.
- Rates should be quoted both in words & figures.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore I/we hereby quote..... % above/below/at par on the estimated cost of Rs.189703.00


Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.


Executive Engineer

Contractor

- The Director, Computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- Sh. Jacob John, J.E. (C)
- Ms. Kavita, J.A.C.T. to ensure the display of the tender notice on University website
- Notice Board.


Executive Engineer