

**ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI – 110 007**

Ref.No.UE/ 31 /DU/ M- 53 (2020-2021)

Dated: 17/1/2020

NOTICE INVITING QUOTATIONS

Sealed percentage rate quotations are here by invited from the contractors enlisted with C.P.W.D., MES, Railways and working contractors of Delhi University for the work "Provision of EWC, sanitary fittings at A-1/3, Maurice Nagar, University of Delhi." So as to reach the office of the undersigned upto 3.00 p.m. on 24/1/2020

SLNo	Description	Qty	Unit	Rate	Amount
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
1.1	For thickness of tiles 10 mm to 25 mm	1	sqm	54.85	54.85
2	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	1	each	668.15	668.15
3	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	2	cum	138.85	277.70
4	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
4.1	W.C. pan with ISI marked white solid plastic seat and lid	1	each	5260.95	5260.95
5	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	1	sqm	926.90	926.90
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
6.1	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources).	1	cum	6788.60	6788.60
7	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 :				
7.1	15 mm nominal bore	1	each	418.95	418.95
8	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
8.1	15mm nominal bore	1	each	532.00	532.00
	Total				14928.10
	Say				14928.00

Conditions:

1. The work is to be completed within 07 days time.
2. 1.50% water /electricity charges will be recovered.
3. C.P.W.D. specifications will be followed.
4. Rates should be quoted both in words & figures.
5. Undersigned reserves the right to reject any or all the quotations without assigning any reason therefore.

Executive Engineer

1. I / We hereby quote.....% above / below / at par the estimated cost of Rs.14,928.00 to execute the above work.
2. I / we hereby undertake that my / our agency have not been blacklisted / debarred in any Govt. Organization since last 3 years.

(Contractor)

1. The Director, Computer Centre with a request to display the Notice inviting spot quotation on the University Website.
2. Mrs. Kavita, J.A.C.T. to ensure the display of the tender /quotation notice on the University website.
3. Notice Board.

Executive Engineer