

**ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007**

Ref. No. UE/ 271

/DU/M-54 (2014-15)

Dated 2-3-15


NOTICE INVITING QUOTATIONS

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Repair of parapet and facia at C-31 and C-33 (29-31) Probyn Road, University of Delhi. "So as to reach the office of the undersigned upto 3.00 P.M. on.....3-3-15

Sl. No.	Description of items	Qty	Unit	Rate	Amount
1	Add for plaster drip course/ groove in plastered surface or moulding to R.C.C. projections.	30	metre	27.85	836.00
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1 cement : 4 fine sand)	40	sqm	221.15	8846.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	400	sqm	9.00	3600.00
4	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	400	sqm	56.55	22620.00
5	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in- charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.	60	sqm	148.65	8919.00
6	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	6	cum	123.85	743.00
7	P/f pidicrete MPB (1 coat) & pidifin 2K (2coats) coating over brick wall as directed by Engineer-in Charge.	10	sqm	480.00	4800.00
8	Repair ceiling plaster RCC surface i/c removing the loose concrete and applying water proofing treatment with Dr. Fixit compound the rough surface the ceiling plaster bottom layer 1:3 (1cement: 3 C. sand) and top layer 1:3 (1cement: 3 fine sand) total thickness at the plaster 15 to 25 mm	36	sqm	345.00	12420.00
Total					62784.00

Condition:

- The work should be completed in 15 days.
- 1.5 % water charges will be deducted.
- Rates should be quoted both in words & figures.
- CPWD specification in force will be followed.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.


Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.62784/-

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

cc 1. To Direct Computer Cent with a request to display the notice Inviting Quotation at Delhi University
2. Su Ja to the JE (C)
3. Mr. Karita JACT to ensure the display of tender notice in university website