

**ENGINEERING DEPARTMENT  
UNIVERSITY OF DELHI  
DELHI-110007**

Ref. No. UE/ 184

/DU/M- 01 (2015-2016)

dated 13/8/15

**NOTICE INVITING QUOTATIONS**


Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Repair of wooden partition, replacing damaged tile in flooring and distemping painting the class room 309, 310A, 310B at 1st Floor Arts Faculty Extn. Building, University of Delhi, Delhi-110007. So as to reach the office of the undersigned upto 3.00 P.M. on 18-8-15"

Sl. No.	Description of items	Qty	Unit	Rate	Amount
1	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete : 2nd class teak wood 50x12 mm	20	mtr	148.10	2962.00
2	Providing and fixing 4mm thick coir veneer board, ISI marked IS : 14842, plain lining with necessary screws, priming coat on unexposed surface etc., complete.	15	sqm	914.55	13718.00
3	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigment etc., complete.	15	sqm	822.10	12332.00
4	Applying priming coat : With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)	15	sqm	30.75	461.00
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	90	sqm	63.05	5675.00
6	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1 cement : 4 fine sand)	2	sqm	221.15	442.00
7	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1	cum	123.85	124.00
8	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	3	each	1027.20	3082.00
9	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead : Of area 3 sq. metres and below	1	each	49.60	50.00
10	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators, side /top /centre hung, with beading and all members such as F7D, F4B, K11 B and K12 B etc. complete of standard rolled steel sections, joints mitred and flash butt welded and sash bars tenoned and riveted, including providing and fixing of hinges, pivots, including priming coat of approved steel primer, but excluding the cost of other fittings, complete all as per approved design, (sectional weight of only steel members shall be measured for payment). Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	5	kg	105.10	526.00
11	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm	2	sqm	651.40	1303.00
12	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : 100 mm	1	each	23.55	24.00

13	Tucking C.C.flooring i/c disposal of malba with in 50 mtr lead	15	sqm	16.33	245.00
14	Dismantling tile flooring and cleaning the floor	15	sqm	27.00	405.00
				<b>Total</b>	<b>41349.00</b>

Condition:

- 1 The work should be completed in 30 days.
- 2 1.5% water charges will be deducted.
- 3 Rates should be quoted both in words & figures.
- 4 The contractor must visit the site before quoting his rates.
- 5 CPWD specification in force will be followed.
- 6 Contractor has to make the arrangement for taking out office/class room furniture for execution of work and re-setting the same after execution of work if required.
- 7 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

  
Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.41349/-


Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3  
(Contractor)

Copy to:

- 1 The Director, Computer Center with a request to display the Notice Inviting quotation the Delhi University Website.
- 2 Sh. Vinod Kr. Jain, A.E. (C)
- Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 4 Notice Board

Agency

  
Executive Engineer

Address

Contract No.