

**ENGINEERING DEPARTMENT  
UNIVERSITY OF DELHI  
DELHI-110007  
NOTICE Re-INVITING QUOTATIONS  
(2015-2016)**

Ref. No. UE/ **338**

/DU/M-57

dated **1-12-15**

Sealed percentage rate quotations are hereby Re-invited from the contractors enlisted with CPWD, MES, Railways and any Govt./ public sector undertaking and working contractor of Delhi University for the work "P/L kota stone flooring at C-85 (New Allotment), Reids Line Colony, University of Delhi." "So as to reach the office of the undersigned upto 3.00 P.M. on **01/12/15**

| S. No | Description of Items  | Unit | Qty  | Rate         | Amount       |
|-------|---|------|------|--------------|--------------|
| 1     | Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) 25 mm thick  | sqm  | 30   | 1141.4       | 34242        |
| 2     | Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15 mm nominal bore   | each | 4    | 459.5        | 1838         |
| 3     | Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 a) 15 mm nominal bore   | each | 4    | 507.7        | 2031         |
| 4     | Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.   | sqm  | 2    | 1191.25      | 2383         |
| 5     | Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall, 15 mm dia nominal bore  | mtr  | 2    | 215.1        | 430          |
| 6     | Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws 35 mm thick shutters, with ISI marked M.S. pressed butt hinges bright finished of required size, Second class teak wood | sqm  | 4    | 3063.05      | 12252        |
| 7     | 18mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).  | sqm  | 10   | 240.55       | 2406         |
| 8     | Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete 250x16 mm   | each | 3    | 166.2        | 499          |
| 9     | Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete 200x10 mm  | each | 8    | 58.65        | 469          |
| 10    | Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete 100 mm  | each | 10   | 26.4         | 264          |
| 11    | Distemping with 1st quality acrylic washable distemper (ready made) of approved manufacturer and of required shade and colour complete. As per manufacturer's specification. One or more coats on old work  | sqm  | 80   | 28.8         | 2304         |
| 12    | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)   | cum  | 1.5  | 4004         | 6006         |
| 13    | Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for separately) Second class teak wood   | cum  | 0.03 | 91496.9      | 2745         |
| 14    | P/F fancy aluminium pipe/ curtain rods with brackets / side funnels of size upto 32 mm dia pipe (heavy type) with necessary screws etc all complete.  | mtr  | 12   | 365          | 4380         |
| 15    | Disposal of building rubbish/ malb/ similar unserviceable/ malba / similar unserviceable, dismantled or waste material by mechanical means, i/c loading & unloading as approved by Engineer-in-charge i/c cartage upto 12 km  | cum  | 3    | 305.45       | 916          |
|       |   |      |      | <b>Total</b> | <b>73165</b> |

**Condition:**

- The work should be completed in 20 days.
- 2 % water/ electric charges will be deducted.
- Rates should be quoted both in words & figures.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore
- SC/ ST contractors should enclose copies of attested caste certificate otherwise their quotation will not be considered.
- Contractor should enclose the copy of Labour Licence, Registration with EPFO, ESIC & BOCW Welfare Board otherwise their quotation will not be considered

i/we hereby quote..... % above/below/at par on the estimated cost of Rs.73165.00

**Undertaking:**

i/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

Contractor

- The Director, Computer Center with a request to display the Notice Inviting Quotation on the Delhi University Website.
- Ms. Kavita, J.A.C.T. to ensure the display of the tender notice on University website
- Notice Board.

*SI*  
Executive Engineer

*Ph*  
Executive Engineer