

**Office of the Executive Engineer
South Campus, University of Delhi**

SC -

21.01.2016

Sealed percentage rates quotations are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractors of Delhi University for the work of, "**Replacement of damaged water storage tank on terrace of Saramati Hostel, SDC..**" so as to reach the office of the undersigned on **29.01.2016** by 3.00 P.M. The quotations shall be opened on the same day at 3.30 P.M.

SLNo	Description	Qty	Unit	Rate	Amount
1	Dismantling the existing damaged water storage tank and depositing to the Engineering Office etc. complete.	1	job	800.00	800.00
2	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :				
	40 mm nominal bore	4	each	584.20	2337.00
3	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :				
	25 mm nominal bore	5	each	446.95	2235.00
4	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required :				
a	25 mm nominal bore	2	each	366.80	734.00
b	40 mm nominal bore	2	each	482.95	966.00
5	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, ISI : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	7000	per litre	6.30	44100.00
6	Providing and fixing PTMT Ball cock of approved quality, colour and make complete with Epoxy coated aluminium rod with L.P./H.P.H.D. plastic ball.				
a	25 mm nominal bore, 152mm long, weighing not less than 440 gms	6	each	551.50	3309.00
b	P/f tank nipple 40mm.	6	Nos.	350.00	2100.00
c	P/f tank nipple 25mm.	6	Nos.	180.00	1080.00
d	P/f G.I. elbo 25mm	6	Nos.	45.00	270.00

e	P/f G.I. socket 25mm	5	Nos.	45.00	225.00
Total					58156.00

Conditions

1. The work is to be carried out as per CPWD specifications.
2. The time allowed to complete the work **10 days**.
3. 1% water charges to be deducted from the bill.
4. The rate quoted should be inclusive of all taxes and duties & should be written both in words and figures.
5. The contractor should see the site before quoting the rate.
6. Undersigned reserves the right to reject any or all the quotations without assigning any reason thereof.
7. The contractors are required to submit a copy of Labour Licence Registration with EPFO, ESIC and BOCW Welfare Board.

Executive Engineer
South Campus

I/we _____ hereby agree to execute the above
@ _____% Above/Below/At Par the estimated cost.

Signature _____

Name _____

Address _____

Telephone _____