

**Engineering Department
University of Delhi
Delhi-110007**

Ref No:-CE/

196

DU/EM- (2022-2023)

Dated

21/7/22

NOTICE INVITING SHORT QUOTATION

Sealed percentage rate spot quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Providing and fixing of sewage submersible pump in the Underground tank and repairing of steel work and other allied work to be carried out at Gwyer Hall, University of Delhi 'So as to reach the office of the undersigned upto 3.00 P.M. on... 25/7/22..

S.No	Description of items	Qty	Unit	Rate	Amount
1	Providing and fixing of 7.5 HP sewage submersible pump 3 phase 440 volt AC supply having duty 3000 RPM complete with all accessories discharge range 1500-400 including making connection etc as reqd. at site(model. No STPCS7.5 2-22) (Crompton) (Gwyer Hall)	2	nos	77507	155014
2	Supplying and Fixing of 4" PVC corrugated pipe for the existing pump etc as reqd. at site	30	mtr	550	16500
3	Providing and Fixing of water level sensor for the existing pump etc as reqd. at site (KSB)	2	nos	2500	5000
4	Providing and fixing G.I. Union, socket, nipple, band for G.I. pipe including cutting and threading the pipe and making long screws etc	2	job	2500	5000
5	S/F testing & commissioning of panel board 3 phase 4 wire system 415v, AC supply Incoming 1 no.VM 0-500v 1 no.AM meter Analog 0-20V with in built selector switch 0-20 amp TP MCB - 32 amp - 1 nos Outgoing 1 nos DOL starter 1 no. single phase preventer 1 no OLR 13-20 amp water level points , indication light and ON/OFF button complete with all accessories as per reqd. at site	2	nos	12000	24000
6	Supplying and fixing of 5 ton 3m heavy duty chain pulley ISI mark for the motor taking out from the tank etc as reqd. at site	1	job	40116	40116
7	Supplying and fixing of PVC box of size 18" x 18" complete with all accessories i/c suitable clamps, suitable bakelite sheet, brass screws , washers and 1 nos TPN MCB capacity i/c making connection etc as reqd. at site.(make Syntex)	1	Nos	8000	8000
8	Supplying , fixing and laying of one number PVC insulated and PVC sheathed /XLPE aluminium armoured conductor power cable confirming to 1.1 KV grade of following size direct in ground including excavation, sand cushioning , protective covering ,refilling the same etc as reqd. 4 x 16 sqmm	185	mtr	692	128020
9	S/F 3 x 2.5 sqmm PVC insulatd PVC sheathed copper conductor flexible cable i/c connection etc as reqd.	200	mtr	210	42000
10	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the same etc as reqd. at site 100 mm	12	mtr	1815	21780
11	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	25	sqm	859.35	21483.75
12	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	0.5	cum	6788.6	3394.3
13	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand) 6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	0.5	cum	5520.3	2760.15
		0.5	cum	6376.25	3188.125
		6	sqm	227.35	1364.1
14	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	20	sqm	161.15	3223

15	Distemping with Ist quality Acrylic distemping of approved manufacture of required shade, two or more coats, i/c removing of dry or oil bound distemper water proofing cement paint by the like by scraping, sand papering, p/a white cement based putty over the wall surface and applying primer with water thinnable cement primer on wall surface etc complete in all respect to get a smooth and even finish as directed by the Engineer-in-charge.	40	sqm	145.17	5806.8
16	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	55	kg	131	7205
17	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old work	10	sqm	79.95	799.5
18	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m.	115	sqm	24.35	2800.25
19	Disposal of building rubbish / malba / similar unserviceable, dismantlor waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	5	cum	138.85	694.25

Total 498149.23
Say Total 498149.00

Condition:

- 1 The work should be completed in 07 days.
- 2 Rates should be quoted both in words & figures.
- 3 The contractor must visit the site before quoting his rates.
- 4 CPWD specification in force will be followed.
- 5 Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

Chief Engineer

I/we hereby quote.....% above/below/at par on the estimated cost of **Rs. 498149.00/-**

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- 1 The Director, Computer Center with a request to display the Notice Inviting quotation on the Delhi University Website.
- 2 Sh. Vijender Meena, J.E. (C)
- 3 Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- 4 Notice Board


Chief Engineer