Office of the Executive Engineer

SC-December 21, 2015

Sealed percentage rate quotations are here by invited from the contractors enlisted with CPWD, MES, Railways and working contractors of Delhi University for the work of "Repair and painting work in vacant flat no. 4, type-III, block-III, new housing unit at South Campus University of Delhi." so as to reach the office of undersigned on dated 31.12.2015 by 3.00P.M. the quotations will be opened on the same day at 3:30P.M.

SLNo	Description	Qty		Unit	Rate	Amount
1	Providing and laying in position cement concrete					
	of specified grade excluding the cost of					
	centering and shuttering - All work up to plinth					
	level:					
	1:4:8 (1 Cement : 4 coarse sand : 8 graded					
	stone aggregate 40 mm nominal size)		.35	cum	3920.65	1372.00
2	Providing and fixing aluminium sliding door bolts,					
	ISI marked anodised (anodic coating not less					
	than grade AC 10 as per IS : 1868), transparent					
	or dyed to required colour or shade, with nuts					
	and screws etc. complete : 300x16 mm		2	each	215.30	431.00
3	Providing and fixing aluminium tower bolts, ISI			еасп	215.30	431.00
3	marked, anodised (anodic coating not less than					
	grade AC 10 as per IS : 1868) transparent or					
	dyed to required colour or shade, with necessary					
	screws etc. complete :					
	osiono otti oompioto i					
	200x10 mm		2	each	76.40	153.00
4	Providing and fixing aluminium handles, ISI					
	marked, anodised (anodic coating not less than					
	grade AC 10 as per IS: 1868) transparent or	-				
	dyed to required colour or shade, with necessary	'				
	screws etc. complete :					
	125 mm		2	each	66.95	134.00
5	Providing and fixing fly proof stainless steel		_	odon	00.00	101.00
	grade 304 wire gauge, to windows and					
	clerestory windows using wire gauge with					
	average width of aperture 1.4 mm in both					
	directions with wire of dia. 0.50 mm all complete.					
<u> </u>	With 12 mm mild steel U beading		1	sqm	1288.05	1288.00
6	Provoding & fixing wiper for door shutter		4	Noo	254.00	254.00
7	complete. P/f extra wooden board shelves in wooden		1	Nos.	251.00	251.00
1	cupboards/below kitchen plate form i/c					
	painting/polishing etc. complete.		2	Nos.	250.00	500.00
8	Kota stone slab flooring over 20 mm (average)			INUS.	230.00	300.00
	thick base laid over and jointed with grey cement					
	slurry mixed with pigment to match the shade of					
	the slab, including rubbing and polishing					
	complete with base of cement mortar 1 : 4 (1					
	cement : 4 coarse sand) :					
	•					

	25 mm thick	5	sqm	1071.70	5359.00
9	Kota stone slabs 20 mm thick in risers of steps,				
	skirting, dado and pillars laid on 12 mm				
	(average) thick cement mortar 1:3 (1 cement: 3				
	coarse sand) and jointed with grey cement slurry				
	mixed with pigment to match the shade of the				
	slabs, including rubbing and polishing complete.				
	and the grant grant grant grant grant	1	sqm	1100.85	1101.00
10	Tile cleaning	30	mtr	30.00	900.00
11	Providing and fixing on wall face unplasticised	- 00		00.00	000.00
l · ·	Rigid PVC rain water pipes conforming to IS:				
	13592 Type A, including jointing with seal ring				
	conforming to IS: 5382, leaving 10 mm gap for				
	thermal expansion, (i) Single socketed pipes.				
	thermal expansion, (i) Single socketed pipes.				
	110 mm diameter	11	metre	218.60	2405.00
12	Providing and fixing on wall face unplasticised -	- 11	mene	210.00	2403.00
12					
	PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes				
	conforming to IS: 13592 Type A, including				
	jointing with seal ring conforming to IS: 5382,				
	leaving 10 mm gap for thermal expansion.				
	Circula to a suith asst place				
10	Single tee without door	1	aaah	244.95	245.00
13 14	110x110x110 mm	!	each	244.93	245.00
14	Bend 87.5°	2	aaah	160.05	404.00
15	110 mm bend	3	each	160.25	481.00
15	Distempering with oil bound washable distemper				
	of approved brand and manufacture to give an				
	even shade :				
	New work (two or more coats) over and including				
	water thinnable priming coat with cement primer	0.40		70.05	40440.00
16	Deinting with comtacting anomal point of approved	240	sqm	79.65	19116.00
16	Painting with synthetic enamel paint of approved				
	brand and manufacture to give an even shade:				
	Two or more coats on new work	90	sqm	63.05	5675.00
17	Providing and applying white cement based	30	Sqiii	03.03	3073.00
l' <i>'</i>	putty of average thickness 1 mm, of approved				
	brand and manufacturer, over the plastered wall				
	surface to prepare the surface even and smooth				
	complete.	180	sqm	85.40	15372.00
18	Repairs to plaster of thickness 12 mm to 20 mm		Sqiii	03.40	13372.00
10	in patches of area 2.5 sq. meters and under,				
	including cutting the patch in proper shape,				
	raking out joints and preparing and plastering the				
	surface of the walls complete, including disposal				
	of rubbish to the dumping ground within 50				
	metres lead :				
	With cement mortar 1:4 (1 cement : 4 fine sand)	10	cam	224 45	2242.00
19	Renewing glass panes, with putty and nails	10	sqm	221.15	2212.00
19	wherever necessary including racking out the old				
	putty:	4	cam	654.40	651.00
	Float glass panes of thickness 4 mm	1	sqm	651.40	651.00

20	Removing dry or oil bound distemper, water				
	proofing cement paint and the like by scrapping,				
	sand papering and preparing the surface smooth				
	including necessary repairs to scratches etc.				
	complete.	230	sqm	9.00	2070.00
21	Repoar of door/window/racks etc. steel or wood				
	as per the requirement with necessary fittings				
	etc. complete.	5	each	350.00	1750.00
22	Dismantling stone slab flooring laid in cement				
	mortar including stacking of serviceable material				
	and disposal of unserviceable material within 50				
	metres lead.	3	sqm	88.50	266.00
23	Dismentlingkota stone skirting mannualy by				
	using cutting machine with making liner chases				
	etc. comp. (for safty of wall tiles)	10	mtr	80.00	800.00
24	Providing and fixing white vitreous china				
	pedestal type water closet (European type W.C.				
	pan) with seat and lid, 10 litre low level white				
	P.V.C. flushing cistern, including flush pipe, with				
	manually controlled device (handle lever),				
	conforming to IS: 7231, with all fittings and				
	fixtures complete, including cutting and making				
	good the walls and floors wherever required :				
	W.C. pan with ISI marked white solid plastic seat				
	and lid	1	each	3189.75	3190.00
25	P/f CP brass jet spray of approaved make for				
	EWC pan with nut bolts etc. complete.	1	each	479.00	479.00
26	Taking yout Indian W/c	1	nos.	150.00	150.00
27	Providing and fixing G.I. pipes complete with G.I.				
	fittings and clamps, i/c cutting and making good				
	the walls etc.			101.05	0.1=0.00
	15 mm dia nominal bore	12	metre	181.35	2176.00
28	Making connection of G.I. distribution branch				
	with G.I. main of following sizes by providing and				
	fixing tee, including cutting and threading the				
ļ	pipe etc. complete :	4		220.00	220.00
	25 to 40 mm nominal bore	1	each	338.90	339.00

29	Providing and fixing brass stop cock of approved				
	quality:				
	15 mm nominal bore	1	each	259.85	260.00
30	Painting G.I. pipes and fittings with synthetic				
	enamel white paint with two coats over a ready				
	mixed priming coat, both of approved quality for				
	new work :				
	15 mm diameter pipe	12	metre	8.60	103.00
31	Providing and fixing G.I. Union in G.I. pipe				
	including cutting and threading the pipe and				
	making long screws etc. complete (New work):				
	15 mm nominal bore	3	each	155.65	467.00
32	Providing and fixing C.P. brass bib cock of				
	approved quality conforming to IS:8931:				
	15 mm nominal bore	1	each	458.40	458.00
33	Providing and fixing C.P. brass long nose bib				
	cock of approved quality conforming to IS				
	standards and weighing not less than 810 gms.				
	15 mm nominal bore	1	each	795.20	795.00
34	Making hole up to 20x20 cm and embedding				
	pipes up to 150 mm diameter in masonry and				
	filling with cement concrete 1:3:6 (1 cement : 3				
	coarse sand 6 graded stone aggregate 20 mm				
	nominal size) including disposal of malba.				
	·	1	metre	119.45	119.00
	Total	·	•		71068.00

Conditions

- 1. The work is to be carried out as per CPWD specifications.
- 2. The time allowed to complete the work 25 days.
- 3. 1% water charges to be dedcuted from the bill.
- 4. The rate quoted should be inclusive of all taxes and duties & should be written both in words and figures.
- 5. The contractor should see the site before quoting the rate.
- 6. Undersigned reserves the right to reject any or all the quotations without assigning any reason thereof
- 7.The contractors are required to submit a copy of Labour Licence Registration with EPFO, ESIC and BOCW Welfare Board.

	South Campus
I/we	hereby agree to execute the above work
@	% Above/Below/At Par the estimated cost.
	Signature
	Name
	Address
	
	Telephone