ENGINEERING DEPARTMENT

UNIVERSITY OF DELHI

DELHI-110007

Ref. No. CE/ 9 /DU/M- 73 (2025-2026) dated 28/4/25

NOTICE INVITING SPOT QUOTATION

Sealed percentage rate spot quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work **"Making all the washrooms operational at Ist, 2nd, 3rd Floor and corner ground for the function of marathon on "One Nation, One Election" at Rugby Seven Sports Complex, University of Delhi.'**So as to reach the office of the undersigned upto 1.00 P.M. on.....28/4/25

Sl. No.	Description of items	Qty	Unit	Rate	Amount
1	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	15.00	No.	146.30	2194.50
2	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 : 15mm nominal bore	8.00	No.	500.35	4002.80
3	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour. 15 mm nominal bore with 45 cm length.	25.00	No.	112.45	2811.25
4	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge.	9.00	No.	886.25	7976.25
5	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer) with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make in all colours & shade in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1cement: 3 coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	5.00	Sqm	1466.50	7332.50
6	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	5.00	Sqm	60.50	302.50
7	P/F white vitreous china Round Under Counter Wash Basin (Hindware Catalogue No.10065) with cp brass 32mm waste jali, Thread, white cement,etc complete as per direction of engineer in charge.	2.00	No.	5695.00	11390.00
8	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface).	250.00	Sqm	111.60	27900.00
9	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats.	300.00	Sqm	116.05	34815.00
10	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	550.00	sqm	20.85	11467.50
11	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	200.00	Sqm	123.85	24770.00
12	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. :Concealed work, including cutting chases and making good the walls etc. 15 mm nominal dia Pipes	5.00	metre	441.15	2205.75
13	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	8.00	No.	1025.65	8205.20
14	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete	10.00	No.	233.10	2331.00
15	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	9.00	No.	325.95	2933.55
16	Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick, fixed in urinalpartitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finishedsmooth. Granite Stone of approved shade	3.00	sqm	3216.90	9650.70
17	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall 25 mm nominal outer dia. Pipes.	12.00	mtr	408.55	4902.60

	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) 25 mm nominal bore	2.00	No.	369.35	738.70
19	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	2.00	No.	532.35	1064.70
20	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge. Note - item to be applicable in urban areas having directions for restricted hours for movement/ plying of load carrying motor vehicle of 3.5 cum or more.	10.00	Cum	411.30	4113.00
21	P/F solid plastic soft close seat cover for dual flush WC of approved quality as per direction of Engineer in charge.	9.00	No.	1731.00	15579.00
22	Providing and fixing 2 Way Bib Cock with Wall Flange of 15 mm nominal bore ARI-CHR-39041 (Jaquar make) etc complete as per direction of Engineer-in-charge	15.00	No.	2773.00	41595.00
23	P/F JAQUAR SIAMP LEMON FLUSH PLATE 100% BRIGHT CHROME SIAMP PARTCODE- 10008492 approved as per direction of Engineer in charge.	35.00	No	3852.00	134820.00
24	Providing and fixing Concealed cistern Ball cock JAQUAR SIAMP MODEL CONCEAL TANK INLET FLOAT VALVE - PE-SIAMPIN-01 for concealed flushing of approved quality and make as per direction of Engineer-in-charge	9.00	No.	2980.00	26820.00
25	Providing and fixing Concealed cistern Brass Ball valve Jaquar Conceal Tank Old Model Angle Valve Model PE 240 of approved make as per direction of Engineer-in-charge	7.00	No.	1707.00	11949.00
26	Providing and fixing Stainless Steel Square Door Lever Internal Mortise Handle Lock with Key Cylinder of approved make and quality with necessary screws etc. complete. as per direction of Engineer in charge	5.00	No.	2645.00	13225.00
27	Providing and fixing Concealed cistern Syphon JAQUAR SIAMP MODEL CONCEAL TANK OUTLET VALVE OUTFLOW VALVE - PE-SIAMPOF-02 of approved quality and make as per direction of Engineer-in-charge	8.00	No.	2637.00	21096.00
28	Repair of wall mounted EWC leakage seepage by taking out the existing EWC and refixing the same after repair i/c changing the nut bolts, rubber washer, pipe connector, coupler etc. complete as per direction of Engineer in charge	15.00	No.	2758.00	41370.00
29	P/F urinal sensor kit of approved make (HINDWARE URINAL SENSO ART KIT Electrn. Sensor Circuit & Solenoid Valve PART CODE PE-H 506092) complete in all respect as per direction by Engineer-in Charge.	8.00	No.	12502.00	100016.00
30	Providing and fixing Urinal Without Sensor With Fixing Accessories, Size: 480x300x740 mm Jaquar URS-WHT-13255 with Sensor Flush Valve Jaquar SNR-CHR-51097 for Urinal Complete with Installation Kit (Battery Operated) Suitable for Urinal complete as per direction of Engineer in charge.	2.00	No.	27738.00	55476.00
31	Taking out existing Urinal Pot, p/f urinal brackets, connection and refix after cleaning with roff cera clean etc complete as per Direction of Engineer-in-charge.	8.00	No.	1003.00	8024.00
32	Providing and fixing Hand Shower (Health Faucet) with 8mm Dia 1.2 Meter Long Flexible Tube and Wall Hook (ALD-CHR-577)make as per direction of Engineer-in-charge	25.00	No.	2354.00	58850.00
33	P/F C.P. brass push pillar tap 15 mm nominal bore of Jaquar make no. PRS-CHR-031 as per direction of Engineer in charge.	8.00	No.	3287.00	26296.00
34	Providing and fixing GENIQE SS304 GRADE Floor Square Trap jali 5" (AK-S-127) make as per direction of Engineer-in-charge	40.00	No.	289.00	11560.00
35	Replacing broken PVC/UPVC butt hinges and refix door same et.c complete as per direction of Engineer-in-charge.	8.00	No.	1398.00	11184.00
				Total	**748967.50**

Condition:

1. The work should be completed in days.
2. 1.5% water charges will be deducted.
3. Rates should be quoted both in words & figures.
4. The contractor must visit the site before quoting his rates.
5. CPWD specification in force will be followed.
6. Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

Executive Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of **Rs.748967.50/-**

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

1. Sh Rampal , A.E. (C)
2. Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
3. Notice Board

Executive Engineer