

**ENGINEERING DEPARTMENT
UNIVERSITY OF DELHI
DELHI-110007**

Ref. No. CE/

265

/DU/M- 06 (2022-2023)

dated

8/9/22

NOTICE INVITING QUOTATION

Sealed percentage rate quotation are hereby invited from the contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for the work "Repair/ improvement toilet etc. at Canteen (Cafeteria) DSE Complex, University of Delhi. 'So as to reach the office of the undersigned upto 3.00 P.M. on..... 15/9/22

Sl. No.	Item	Qty	Unit	Rate	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix [i/c equivalent designmix]	0.5	cum	1072.80	536.40
2	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	1	each	5421.50	5421.50
3	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	3	metre	305.05	915.15
4	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Shoe (Plain) 110 mm Shoe	3	each	113.80	341.40
5	Providing and fixing uplasticised PVC connection pipe with brass unions : 30 cm length 15 mm nominal bore	3	each	72.85	218.55
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
6.01	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.5	cum	6788.60	3394.30
6.02	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	1	cum	5520.30	5520.30
7	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete : For pipes 100 to 250 mm diameter	1	each	623.50	623.50
8	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	5	sqm	926.90	4634.50
9	Disposal of leaves, garbage, silt kooda (waste items) etc. i/c loading and unloading charges out of the University campus.	1	trip	2985.00	2985.00
				Total	24590.60
				Say	24591.00

Condition:

- The work should be completed in 5 days.
- 1.5% water charges will be deducted.
- Rates should be quoted both in words & figures.
- The contractor must visit the site before quoting his rates.
- CPWD specification in force will be followed.
- Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore.

Assistant Engineer

I/we hereby quote..... % above/below/at par on the estimated cost of Rs.24591/-

Undertaking:

I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to:-

- Sh. V.K. Meena, J.E. (C)
- Mrs. Kavita, JACT to ensure the display of the quotation notice on University website.
- Notice Board

Assistant Engineer